



CURRENT PROJECTS

US 160 Wilson Gulch Road Extension - 19902

Budget: \$7,153,458 (CDOT: \$4,200,000; La Plata County: \$1,304,000; City of Durango: \$2,355,921; SUIT ROW)

Funding Type: RAMP

Ad Date: September 2014

Awarded: Oldcastle SW Group, Inc.

This RAMP Project is managed by the City of Durango. It will construct a connector road between the US 160 Interchange and the Grandview development. The roadway will serve as a frontage road for US Highway 160 from Three Springs Blvd to the Grandview Interchange, a distance of approximately 1.1 miles. Construction began January 26, 2015 and will be completed in the spring of 2016.



US 160 W. Wildlife Crossing at Dry Creek - 20430

Budget: \$6,546,331

Funding Type: HSIP

Ad Date: March 2015

Awarded: Crossfire, LLC



This project will consist of improvements for safer wildlife migration east of Durango between mile marker 97 and 98, which includes a large mammal underpass. Wider shoulders and wildlife fencing on either side of the highway is also planned. Construction is underway and will continue into late spring 2016 with a winter suspension.

SH 145 at CR P North of Cortez - 19397

Budget: \$1,912,975 (Montezuma County: \$83,036)

Funding Type: RAMP

Ad Date: May 2015

Awarded: OldCastle SW Group, Inc.

This RAMP project consists of the intersection improvements and turn lanes north of Cortez at County Road P. Minor widening is needed to accommodate additional turn lanes. Construction began September and will conclude in December.



R5 FY15 Bridge Preventative Maintenance - 20305

Budget: \$2,800,000

Funding Type: CBR

Ad Date: December 2014

Awarded: G.A. Western Construction Co.



This RAMP project includes maintenance on Bridges: M-01-C on US 491 at MM 60.919 in Dove Creek, O-05-AW on US 550 MM 36.627 over the Durango Silverton Railroad, P-05-R on SH 172 at MM 19.490 over the Florida River, and 3 on US 160 P-06-D MM 102.223 over the Los Pinos River, P-07-A MM 121.325 over the Piedra River, and P-07-B MM 124.963 over Devil Creek. The scope of work expanded to include the emergency repair of Bondad bridge, P-05-G. This project is expected to be completed early December.

FY 15 Priority Culverts, SH 141 – 20380

Budget: \$2,100,000

Funding Type: Priority Culvert

Ad Date: June 2015

Awarded: American West Construction



This project consists of lining culverts at four locations on SH 141 which are located at MP 41.51, MP 43.49, MP 44.89, and MP 54.91.

Construction began on September 8, 2015. This project has a fixed completion date of March 1, 2016.

SH 172/CR 307 Intersection Improvement- 19740

Budget: \$626,000

Funding: HSIP

Awarded: Tricon2 LLC

This project includes adding a left-turn deceleration lane from SH 172 onto CR 307 (between MP 21.9 and MP 22.4 west of Oxford, which is halfway between the junction with US 160 on the north and the airport to the south). The project increases safety at this intersection that receives increasingly high volumes of large truck traffic.

The project construction is scheduled from September 1 to late November 2015.



SH 151/CR 521 Intersection Improvements- 19762

Budget: \$815,700

Funding: HSIP

Awarded: Tricon2 LLC

This project includes adding a continuous left-turn lane on SH 151, just east of Ignacio, to serve both CR 521 (Buck Highway) to the north and CR 321 to the south; adds shoulders between MP 0.33 and MP 0.73. The project increases safety at this off-set intersection, where an accident history shows a higher incidence of collisions involving left-turning vehicles.

The project construction is scheduled from September 8 to late November.



UPCOMING PROJECTS

SH 172/151 Signalization - 19908

Budget: \$1,800,000 (CDOT: \$1,430,000; La Plata County: \$180,000; Southern Ute Tribe: \$180,000, Town of Ignacio: \$10,000)

Funding Type: RAMP

Awarded: Technology Constructors, Inc.

This RAMP project consists of the signalization and intersection improvements in the Town of Ignacio at the intersection of SH 151 and SH 172. This is a partnership with the Town, La Plata County and the Southern Ute Indian Tribe. This project has a fixed completion date of May 25, 2016 with construction to begin in March.

R5 US 24 SH 17 US 160 Priority Culverts - 20404

Budget: \$961,480

Funding Type: Priority Culvert

Ad Date: April 2016

This project consists of three culverts identified on the Priority Culvert List.

SH 145 Chipseal West Fork North - 21059

Budget: \$ 3.2 million for Construction

Funding Type: Surface Treatment

Ad Date: November 2015

This preventative maintenance project will improve the surface condition of Highway 145 from the West Fork of the Dolores River to south of Rico. CDOT is constructing double chip seals to add years of service life to preventative maintenance projects.

SH 145 MP 76.05 Wall Failure – 20456

Budget: \$1.8M

Funding Type: Wall

Ad Date: Shelf December 2015

Replacement of rock retaining wall on State Highway 145 at MM 76. Project will also address uphill drainage through the replacement of two existing culverts and the addition of one culvert. Guardrail encompassing the wall will be upgraded to the new 31" standard.

SH 145 North of Rico - 20501

Budget: \$218,058 Design, \$ 8.6 million for Construction

Funding Type: Surface Treatment

Ad Date: November 2015

This project starts at the north end of Rico at the bridge over the Dolores River and continues to the summit of Lizard Head Pass. Preventative maintenance work will occur at the bridge followed by a leveling course and overlay. Guardrail will be replaced and pavement markings will be applied. Work will commence in June and finish in October, 2016.



US 491 Cortez to MCR 30 (CR M) - 19399

Budget: \$7,500,000

Funding Type: FSA/RPP/SUR

Ad Date: November 2016

This project involves 3 components. (1) A full-depth reclamation from approximate milepost 26.3 to 27.3. This includes relocation of utilities, replacement of storm sewer system, new median islands and street lighting, and repaving with approximately 8 inches of concrete pavement. (2) Includes the re-alignment of the Lebanon Road (CR 25) with US 491 to improve sight distance and protect turning movements in to, and off of this roadway. (3) A 4" mill and 3" fill from approximate milepost 27.3 to 29.2 (CR M).

US 160 McCabe Creek Pagosa - 19263

Budget: \$7M

Funding Type: Priority Culverts

Ad Date: September 2016

This project consists of replacing the existing culverts on US 160 at MP 143.25, near downtown Pagosa Springs, with a box culvert. Construction to begin in spring of 2017.

SH 184 Narraguinnep Canal 0-02-A Structure – 20645

Budget: \$2M
Funding Type: Culvert Program
Ad Date: June 2016

Project consists of the replacement of 0-02-A located on State Highway 184 between SH 145 and US 491 with a concrete box culvert.



US 550 Durango Sidewalk Ramps MP 21-24, 20439

Budget: \$200, 000 Design
Funding Type: FSA
Ad Date: July 2016



This project will initially construct ADA compliant ramps from 26th Street to 31st Street in the fall of 2016. A second phase of design and construction will follow to improve the corners of 18th Street to 21st Street and 33rd Street to 37th Street. New signals at 17th, 22nd and 32nd will be advertised and constructed under a separate project.

*Note location of pedestrian push button behind wall

US Cribwall Repair MP 67-91 – 20741

Budget: \$1.3M
Funding Type: Walls
Ad Date: May 2016

Replacement of two cribwalls on US 550 at approximate mile marker 68.7.

US 491 MP 36.8, 46.0 & CR BB (MP 45.1) – 20684

Budget: \$ 6.5 million Construction

Funding Type: Surface Treatment

Ad Date: November 2016

This surface treatment project will resurface the roadway from Arriola to Pleasant View and improve the intersection at County Road BB, the number four intersection on the Regional Intersection Priority list.



US 550 San Juan Line to Coal Bank Pass – 21056

Budget: TBD

Funding Type: Surface Treatment

Ad Date: Shelf December 2015

Surface Treatment of US 550 from La Plata/San Juan County Line at MM 49.84 to MM 55.95. Length of Project will vary to fit funding available. Treatment is scheduled to include a 1" leveling course and a 1 ½ inch overlay.

US 160 Mesa Verde Bridge Coating – 19026

Budget: \$294,000

Funding Type:

Ad Date: Shelf project ready for advertisement.

This is a preventative maintenance project that will add a structural coating to the bridge and other components to extend the life of the bridge. Project will paint the bridge to match the recently opened Mesa Verde National Park Visitor's Center.

SH 151 MP 13.36 and SH 84 MP 14.67 Priority Culverts – 20695

Budget: TBD

Funding: Priority Culverts

Ad Date: FY 18

Scoping for this project is planned for 2016 with design to follow. Construction is expected to occur in fall of 2018.

US 550 MP 80.72, MP 80.75 Priority Culverts – 20694

Budget: TBD
Funding: Priority Culverts
Ad Date: FY 17

It is anticipated that these two culverts near the summit of Red Mountain Pass will be removed and replaced with precast concrete box culverts. Currently, the drainage is in combination of concrete box culvert extended with a metal pipe and complete replacement is recommended.

US 160 MP 43.18, MP 150.40, MP 156.34 Priority Culverts – 20693

Budget: TBD
Funding Type: Priority Culverts
Ad Date: FY 18

Asset management project to extend the life of three cross culverts between Cortez and Treasure Falls. The concrete box culverts near the Montezuma County Fairgrounds will be rehabilitated and the culverts between Pagosa Springs and Treasure Falls will be lined. Project design has just started.