

CURRENT PROJECTS

US 491/160 New Mexico to Towaoc - 19202

Budget: \$19,708,000

Funding Type: RAMP- Surface Treatment

Ad Date: April 2014



Full depth reclamation of existing road on the Trail of the Ancients



Leveling course paving at US 160/141 intersection

This is a RAMP Surface Treatment project from the New Mexico Stateline to Towaoc along US 491 and US 160. The funding includes a 1' leveling course and 2' overlay from the state line to the US160/491 intersection (milepost 6.422). A full depth reclamation overlay will then proceed north to Towaoc and ties into the Towaoc to Cortez Resurfacing Project constructed in 2013.

The project was awarded to Skanska USA for \$13,715,000. Work began July 8, 2014. Pipework, including headwalls and wingwalls, have been completed. Earthwork has been seeded and mulched ahead of schedule. Project was suspended in mid-January and construction will resume in early to mid-March. Remaining work includes preventive maintenance on bridges, lighting, full depth reclamation, paving, striping and finishing touches. The 14 mile long project is expected to be completed in August, 2015.

UPCOMING PROJECTS

US 160 Wilson Gulch Road Extension

Budget: \$6,400,000 (CDOT: \$4,288,000; La Plata County: \$180,000; City of Durango: \$180,000)

Funding Type: RAMP

Ad Date: Fall 2014

This is a RAMP Project which will be managed by the City of Durango. It will construct a connector road between the US 160 Interchange and the Grandview development. The roadway will serve as a frontage road for US Highway 160 from Three Springs Blvd to the Grandview Interchange, a distance of approximately 1.1 miles. Design updates will be completed this spring. Advertisement is scheduled for August 2014 with construction wrapping up in 2015.

SH 145 at CR P North of Cortez

Budget: \$1,660,194 (CDOT: \$1,577,185; Montezuma County: \$83,036)

Funding Type: RAMP

Ad Date: 2015

This RAMP project consists of the intersection improvements and turn lanes north of Cortez at County Road P. Minor widening is needed to accommodate additional turn lanes. Design will occur in 2014 with construction in 2015.

SH 172/151 Signalization

Budget: \$1,800,000 (CDOT: \$1,430,000; La Plata County: \$180,000; Southern Ute Tribe: \$180,000, Town of Ignacio: \$10,000)

Funding Type: RAMP

Ad Date: July 2015

This RAMP project consists of the signalization and intersection improvements in the Town of Ignacio at the intersection of SH 151 and SH 172. Design is nearly 90% complete. Construction will begin in September and should finish in November, 2015.

US 160 Bayfield to Yellow Jacket - 19710

Budget: \$8,650,000

Funding Type: Surface Treatment

Ad Date: January 2015

This project consists of 1" levelling course and an HMA overlay. It will include new guardrail, new mailboxes, shoulder gravel, rumble strips, pavement markings and other safety improvements.

US 550 Cribwalls Phase II/III Project- 18928/19305

Budget: \$4M

Funding Type: Rockfall

Ad Date: Summer 2015

The project is located on US 550 from MP 77.0-79.6. The scope of work includes widening the roadway to the west using blasting and scaling so that the centerline is shifted a maximum of 15 feet. Additional work includes the replacement of three cribwalls, two cross-culvert replacements, and guardrail installation.

The project is currently in design and ROW acquisition is in progress. The work is scheduled for the fall of 2015.

US 160 Mancos Hill to Hesperus - 19632

Budget: \$8,250,000

Funding Type: Surface Treatment

Ad Date: January 2015

This project consists of resurfacing and overlay from MP 62 to MP 71.1.

FY 15 Priority Culvert US 160 MP 136.61 - 19791

Budget: \$961,480

Funding Type: Priority Culvert

Re-Ad Date: December 2014

This project consists of the installation of a new culvert on US 160 at MP 136.61.

US 160 W. Wildlife Crossing at Dry Creek - 20430

Budget: \$6,546,331

Funding Type: HSIP

Ad Date: February 2015

This project will consist of improvements for safer wildlife migration east of Durango between mile marker 97 and 98.

US 160 McCabe Creek Pagosa - 19263

Budget: \$5.4M

Funding Type: Priority Culverts

Ad Date: September 2015

This project consists of replacing the existing culverts on US 160 at MP 143.25, near downtown Pagosa Springs, with a box culvert.

R5 FY15 Bridge Preventative Maintenance - 20305

Budget: \$2,800,000

Funding Type: CBR

Ad Date: December 2014 (Award Pending)

This RAMP project includes maintenance on Bridges: J-12-AK one mile outside of Salida, I-12-B location by Big Sandy Creek, K-11-G located East of Doyleville, M-01-C which is by Dove Creek, O-05-AW just north of Hermosa, P-05-R north of Ignacio, P-06-D which is east of Junction US 55, and K-09-C in Saguache County.

US 491 Cortez to MCR 30 (CR M) - 19399

Budget: \$7,500,000

Funding Type: FSA/RPP/SUR

Ad Date: January 2016

This project involves 3 components. (1) A full-depth reclamation from approximate milepost 26.3 to 27.3. This includes relocation of utilities, replacement of stormsewer system, new median islands and street lighting, and repaving with approximately 8 inches of concrete pavement. (2) Includes the re-alignment of the Lebanon Road (CR 25) with US 491 to improve sight distance and protect turning movements in to, and off of this roadway. (3) A 4" mill and 3" fill from approximate milepost 27.3 to 29.2 (CR M).

FY 15 Priority Culverts, SH 141 - 20380

Budget: \$2,100,000

Funding Type: Priority Culvert

Ad Date: June 2015

This project consists of the lining of existing culverts at four locations on SH 141. MP 41.51, MP 43.49, MP 44.89, and MP 54.91.

