



CURRENT PROJECTS

US 160 Wilson Gulch Road Extension - 19902

Budget: \$7,153,458 (CDOT: \$4,200,000; La Plata County: \$1,304,000; City of Durango: \$2,355,921; SUIT ROW)

Funding Type: RAMP

Awarded: Oldcastle SW Group, Inc.

This is a RAMP Partnership Project managed by the City of Durango. Construction is under way to build a connector road between the US 160 Interchange and the Grandview development. The roadway will serve as a frontage road for US Highway 160 from Three Springs Blvd to the Grandview Interchange, a distance of approximately 1.1 miles. Construction began January 26, 2015 and will be completed by June 2016.



US 160 W. Wildlife Crossing at Dry Creek - 20430

Budget: \$6,546,331

Funding Type: HSIP

Awarded: Crossfire, LLC

This safety project consists of a large mammal underpass, wider shoulders, wildlife fencing and other associated improvements for safer wildlife migration east of Durango between mile marker 97 and 98. Construction began summer of 2015 and will be completed fall of 2016. Winter suspension will end April 4, 2016 and construction will resume.



US 550 Cribwalls Phase II/III Project- 18928/19305

Budget: \$4 Million
Funding Type: Rockfall
Awarded: Rock & CO.

The project is located on US 550 from MP 77.0-79.6. The scope of work includes widening the roadway to the west using blasting and scaling so that the centerline is shifted a maximum of 15 feet. Most of the blasting and rock excavation was finished last year. Additional work includes the replacement of three cribwalls, two cross-culvert replacements, and guardrail installation. Construction in 2015 completed all of the work at Sites 2 and 3 (Ouray side) including a concrete cap



at Ruby Walls, MP 89.7, which was damaged by rockfall in 2014. At sites 2 and 3, the project partnered with CDOT Geohazards to remove captured rockfall from the slope above ruby walls as well as SMPA to replace damaged electric poles. This project is currently in winter shutdown and will resume in May with an anticipated completion in late summer 2016.

SH 172/151 Signalization - 19908

Budget: \$1,800,000 (CDOT: \$1,430,000; La Plata County: \$180,000; Southern Ute Tribe: \$180,000, Town of Ignacio: \$10,000)
Funding Type: RAMP
Awarded: Technology Constructors, Inc.

This RAMP Partnership Project consists of signalization and intersection improvements at SH 151 and SH 172 in the Town of Ignacio. This is a partnership with the Town, La Plata County, and the Southern Ute Indian Tribe. Construction began March 21, 2016 and there is a fixed completion date of May 25, 2016. Current construction activities include installation of signal poles and mast arms. Ute Street grading is also underway with paving to follow. The 30-day closure of Ute Street began April 11, 2016.

UPCOMING PROJECTS

SH 145 Chipseal West Fork North - 21059

Budget: \$ 3.2 million for Construction
Funding Type: Surface Treatment
Awarded: Oldcastle SW Group, INC.

This preventative maintenance project will improve the surface condition of Highway 145 from the West Fork of the Dolores River to south of Rico. CDOT is constructing double chip seals to add years of service life to preventative maintenance projects. Construction to begin in spring of 2016.

SH 145 North of Rico - 20501

Budget: \$218,058 Design, \$ 8.6 million for Construction
Funding Type: Surface Treatment
Awarded: Elam Construction Incorporated

This project starts at the north end of Rico at the bridge over the Dolores River and continues to the summit of Lizard Head Pass. Preventative maintenance work will occur at the bridge followed by a leveling course and overlay. Guardrail will be replaced and pavement markings will be applied. Work will commence in the summer and conclude in fall 2016.



US 491 Cortez to MCR 30 (CR M) - 19399

Budget: \$7 Million
Funding Type: FSA/RPP/SUR
Awarded: Lawson Construction Co.

Project involves 3 components. (1) Removal of existing asphalt mat, grading and a concrete pavement from approximate milepost 26.3 to 27.3. This includes relocation of utilities, replacement of storm sewer system, new median islands and street lighting, and repaving with approximately 8 inches of concrete pavement. (2) Includes the re-alignment of the Lebanon Road (CR 25) with US 491 to improve sight distance and protect turning movements in to, and off of this roadway. Construction to begin in summer and wrap up late winter 2016.

US 160 Mesa Verde Bridge Coating – 19026

Budget: \$250,000
Funding Type:
Awarded: JITA Contracting

This is a preventative maintenance project that will add a structural coating to the bridge and other components to extend the life of the bridge. Project will paint the bridge to match the recently opened Mesa Verde National Park Visitor's Center. Construction expected to begin summer 2016 and be completed by the end of June 2016.

R5 US 24, SH 17, US 160 Priority Culverts - 20404

Budget: \$961,480
Funding Type: Priority Culvert
Ad Date: April 2016

This project consists of three culverts identified on the Priority Culvert List. All culverts have rust corrosion with perforations and separation in the invert. One culvert is located within this TPR on US 160 at MP 3.67. Construction to begin in fall of 2016 and wraps up in the spring of 2017 after a winter suspension.

SH 184 Narraguinnep Canal 0-02-A Structure – 20645



Budget: \$200,000 (Design) \$2 Million (Construction)
Funding Type: Culvert Program
Ad Date: June 2016

Project consists of the replacement of 0-02-A located on State Highway 184 between SH 145 and US 491 with a concrete box culvert.

US 160 McCabe Creek Pagosa - 19263

Budget: \$7M
Funding Type: Priority Culverts
Ad Date: September 2016

This project consists of replacing the existing culverts on US 160 at MP 143.25, near downtown Pagosa Springs, with a box culvert. Construction to begin in spring of 2017.

US 550 Durango Sidewalk Ramps MP 21-24 - 20439

Budget: \$200,000 Design
Funding Type: FSA
Ad Date: July 2016

This project will initially construct ADA compliant ramps from 26th Street to 31st Street in the fall of 2016. A second phase of design and construction will follow to improve the corners of 18th Street to 21st Street, and 33rd Street to 37th Street. New signals at 17th, 22nd and 32nd will be advertised and constructed under a separate project.



US 550 Cribwall Repair MP 68.7 and 88.76 – 20741

Budget: \$1.3M
Funding Type: Walls
Ad Date: Fall 2016

Replacement of two cribwalls on US 550 at approximate mile marker 68. Construction to begin spring of 2017.

US 550 San Juan Line to Coal Bank Pass – 21056

Budget: \$ 2.8 M
Funding Type: Surface Treatment
Awarded: Oldcastle SW Group, INC.

Surface Treatment of US 550 from La Plata/San Juan County Line at MM 49.84 to MM 55.95. Length of Project will vary to fit funding available. Treatment is scheduled to include a 1" leveling course and a 1 ½ inch overlay. Construction expected to begin in summer 2016.

US 491 Surface Treatment MP 27.3 – MP 36.8 – 20502

Budget: \$ 10 M
Funding Type: Surface Treatment
Ad Date: November 2016

This surface treatment project begins at the end of the concrete pavement at Lebanon Road, approximate mile point 27.3 and extends to mile point 36.8. There will be mill and

fill from mile point 27.3 to 29.2 and then cold in-place recycling from County Road M to SH 184 intersection.

US 491 at County Road S – 21013

Budget: TBD

Funding Type: FSA

Ad Date: Shelf

This intersection is listed as #1 on the region's Intersection Priority List. Survey is almost completed and design will begin soon. Turn lanes will be added and coordination with Montezuma County will be needed for access improvements.